



Complete Cedar Package

1 WALL SYSTEM COMPONENTS

- PRECUT LOG WALL STOCK, PRE-DRILLED
- CAULKING COMPOUND
- LAG BOLTS AND WASHERS
- CEDAR JOINING SPLINES
- CLOSED CELL FOAM SEAL STRIP

2 GABLE ENDS - AS APPLICABLE

- PRECUT LOG WALL STOCK WITH ACCESSORIES ABOVE
- OR
- FRAMED WITH OSB SHEATHING AND LOG SIDING

3 WINDOW AND DOOR BUCKS - PRECUT

- CEDAR

FLOOR SYSTEM

- 4 • BUILT UP GIRDER 3-2X10
- 5 • PRESSURE TREATED SILL PLATE - 2x8 W/ SILL SEAL INSULATION
- 6 • FLOOR JOISTS - 2x10 OR 2x12 AS REQUIRED
- 7 • HEADERS AND DOUBLERS
- 8 • JOIST TIES
- 9 • METAL BRIDGING
- 10 • SUB FLOOR 23/32" T & G* HI-PERFORMANCE OSB
- SKIRTING/FALSE LOG CORNERS
- ENGINEERED FLOORING SYSTEMS AVAILABLE

BASEMENT STAIRS

- TREADS AND STRINGERS 2x12

11 LOFT STAIRS - OPTIONS

- RUSTIC RAILS AND PICKETS
- TREADS AND STRINGERS - 3x11
- OR
- 1/2 LOG TREADS AND RUSTIC STRINGERS

LOFT SYSTEM

- 12 • CEILING JOISTS - ROUND LOG OR RECTANGULAR BEAMS
- 13 • TIE BEAMS - ROUND LOG OR RECTANGULAR BEAMS
- 14 • NECESSARY SUPPORT POSTS
- 15 • 5/4 T & G* SPRUCE SUB FLOOR
- 16 • LOFT RAIL-CEDAR

ROOF SYSTEM - OPTIONS

- 18 • PURLINS OR BEAM RAFTER - LOG OR RECTANGULAR BEAM
- 19 • NECESSARY MATCHING SUPPORTS
- 20 • T & G* PINE ROOF BOARDS
- 21 • ROOF STRAPPING - 2x3
- 22 • 4" RIGID INSULATION
- 23 • ROOF SHEATHING 19/32" OSB
- OR
- CONVENTIONAL - 2x12 RAFTERS OR PREFABRICATED ROOF TRUSSES
- T&G* PINE CEILING
- ROOF SHEATHING 19/32" OSB

ROOFING

- 24 • 15# FELT PAPER
- 25 • ROOF SHINGLES - 30 YEAR ARCHITECTURAL
- 26 • FASCIA WITH DRIP EDGE - GALVANIZED
- 27 • RIDGE VENT

28 WINDOWS AND PATIO DOORS

- ANDERSEN 400 SERIES HI PERFORMANCE WINDOWS & DOORS
- SCREENS

29 EXTERIOR DOORS

- THERMA - TRU INSULATED ENTRY SYSTEM
- 1 LIGHT 2 PANEL

30 PARTITION FRAMING

- STUDS 16" O.C. - 2x4 OR 2x6

31 PARTITION PANELING

- 1" T & G* PINE

32 INTERIOR DOORS

- PASSAGE - PREHUNG KD 6 PANEL PINE OR CUSTOM CEDAR
- CLOSET - LOUVER BIFOLD
- INTERIOR DOOR LOCKSET & HARDWARE

INTERIOR TRIM AND FINISH

- WINDOW AND DOOR TRIM - 1" PINE
- BASEBOARD - 1" PINE
- FRAME GABLE & DORMER INTERIOR FINISH - 1" CEDAR

EXTERIOR TRIM

- 27 • WINDOW & DOOR TRIM - 5/4" CEDAR
- 28 • EAVE TRIM & FASCIA - 1" PINE
- 31 • SOFFIT - T & G*

33 DORMER-OPTIONS

- PRECUT LOG WALL WITH ACCESSORIES ABOVE
- OR
- FRAMED LOG SIDING & FALSE LOG CORNERS

DECK

- 34 • JOISTS - 2x8 PRESSURE TREATED
- 35 • HEADERS - 2x8 PRESSURE TREATED
- 36 • DECKING - 5/4" RADIUS EDGE CEDAR
- 37 • CEDAR RAILS AND BALUSTERS-RUSTIC LOG OR RECTANGULAR LOG
- JOIST HANGERS

PORCH

- DECK AS ABOVE
- 37 • PLATE OR GABLE LOGS - AS MAIN HOUSE
- 38 • SUPPORT POSTS - ROUND OR RECTANGULAR - CEDAR
- 39 • ROOF FRAMING - 2x6 RAFTERS & CEILING JOISTS
- 40 • CEILING - 1" T & G* PINE ROOF SHEATHING 19/32" OSB
- 23 • ROOFING MATERIALS - AS MAIN HOUSE
- 24 • EAVE TRIM - AS MAIN HOUSE

CONSTRUCTION ASSEMBLY PLANS

- CONSTRUCTION INSTRUCTION BOOKLET
- CONSTRUCTION ASSEMBLY PLANS

INDIVIDUAL DESIGN CHOICES

- ROUND OR RECTANGULAR PURLINS
- ROUND OR RECTANGULAR RAFTERS
- HALF LOG OR RUSTIC STAIRS
- ROUND OR RECTANGULAR RAILING
- ROUND OR RECTANGULAR CEILING JOISTS

* TONGUE AND GROVE

WWW.CAROLINALOGCENTER.COM